purchaser in the manner prescribed for default of payment of one-tenth value in clause 5 *supra*.

9. No timber lot shall be permitted to be removed by the purchaser unless it has been paid for in full, calculated at the rates at which the timber is knocked down to him at the time of sale, excluding the 10 per cent deposit paid for the lot at the time of the sale; and no timber shall be removed from the Depot unless a permit is obtained from the Forest Officer in charge of the Depot. The earnest money will not adjusted towards the value of timber, unil 90 per cent of the purchase money over and above the security deposit has been paid.

10. Timber purchased should be removed as early as possible and in no case should it be allowed to remain longer than 90 days after the dates fixed in clause 7 *supra*. Timber not removed after purchase, will remain in the Depot at the risk of the purchaser from the date of the confirmation of the sale.

11. If the timber is not removed within the time allowed, the same may, after ten days' notice to the purchaser, be sold in public auction and the proceeds will be given to the purchaser after defraying all the expenses in connection with the resale.

12. The deposit of Rs. 200 will remain as security for the due fulfilment of all and every one of the terms of sale, on the breach of any of which by the purchaser, the District Forest Officer shall be entitled to forfeit the deposit in whole or in part and in the event of such forfeiture, the sum so forfeited shall be immediately made good by the purchaser so long as the transaction is not finally closed. The security deposit or the balance thereof, if any, shall be returned to the purchaser after the full value of timber purchased has been paid for and the timber fully removed.

H. S. NARAYANA RAO,
District Forest Officer.

SAGAR FOREST DIVISION.

Notification dated 3rd September 1927.

It is hereby notified that the undermentioned Teak trough found unclaimed in Hargoppa District Forest is now in the Range Office, Shikarpur Range. It does not bear any number or mark of any description. Any person having any right to the same is directed to present to the District Forest Officer, Sagar Division within one month from the date of publication of this notice, a written statement of his claims and establish his rights thereto failing which the ownership of the said trough will rest in Government under Section 42 of the Mysore Forest Regulation.

DESCRIPTION.			
	Length.	Girth.	Cft.
One Teak trough	13'-0"	4'-0"	13 Cft.

K. REVANNA,
District Forest Officer.

KOLAR DIVISION.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 2 P.M. on 24th September 1927, for restoring Kurubarahalli minor tank, Reg. No. 61—505, Srinivaspur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1928.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 125 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Kurubarahalli minor tank, Srinivaspur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in words as well as in figures.

Item of work	Per	Quantity	Rate	Cost
BUND.				
Earthwork to bund, watering and tamping ...	C.yd.	2,490		
Turfing to bund	Sq.yd.	2,151		
New stone work	C.yd.	203		
Removing and resetting old stone revetment with new jelly, wherever necessary.	,,	560		
Providing grade stones including figuring and painting, etc., complete.	No.	15		
Index stones	,,	15		
Providing Register number stone with constructive and survey details.	,,	1		
B. M. stones	,,	2		
Gauge stone	,,	1		
Jungle cleaning of prickly piers ...	Grades	10		
Clearing of ant-hills and filling them with sand ...	No.	3		
Examining the leak in the bund and closing the same between C. S. 4 and 5.	Lump	sum		
Total cost for bund ...				
SLUICE.				
Earthwork excavation and filling the same ...	C.yd.	15		
Surki concrete	C.ft.	101		
Burnt brick in surki mortar	,,	345		
Burnt stone slabs 4" to 6" thick	Sq.ft.	110		
Plastering with surki mortar	Sqrs.	3·60		
Providing cast iron pipe of 4" dia. of 27 ft. long ...	R.ft.	27		
Providing wooden plug and rod with locking arrangements.	Lump	sum		
Cutting holes for the orifice slabs	No.	2		
Total cost for sluice ...				
WASTE WEIR.				
Earthwork excavation	C.yd.	149		
Surki concrete	C.ft.	266		
Burnt brick in surki mortar	,,	602		
Burnt stone slabs 4" to 6" thick	Sq.ft.	138		
Surki plastering	Sqrs.	4·95		
New stone work	C.yd.	36		
Providing joggles	Lump	sum		
Total for waste weir ...				
Total ...				
Contingencies at 5 per cent ...				
Grand total ...				

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division up to 2 P.M. on 24th September 1927, for restoring Ammanallur Major tank, Reg. No. 226, Kolar, Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 2 P.M. and 5 P.M.,

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees 425 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Ammannallur Major tank, Kolar Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The quotations should be noted in figures as well as in words.

Items of work	Per	Rate	Quantity	Cost	Total
Bund.					
Earthwork including watering and tamping ...	C.yd.		5,896		
Turfing	S.yd.		6,993		
Old stone revetment with new jelly	C.yd.		324		
New stone revetment with jelly	,,		1,598		
Gravel backing	,,		703		
Providing new grade stones, including cutting figures, painting, etc., complete.	Each No.		34		
Index stones	Each		34		
B.M. Stones including cutting figures and painting ...	,,		2		
Providing new Reg. No. stone including painting ...	,,		1		
Providing new date stone including painting ...	,,		1		
Providing new gauge stone including cutting figures ..	,,		1		
Clearing jungle and prickly pear	Grade		28		
Cutting grips in old bund	,,		28		
Sluices.					
Repairing the sluice and providing new plug and iron rod with locking arrangement.	L. S.		Rs.		
Constructing a waste weir of 115' *long on the left and at R. L.* 50·00.					
Earthwork excavation and using the same to flank bund.	C.yd.		194		
Concrete in surki mortar	C.ft.		740		
Burnt brick in surki mortar	,,		2,491		
Burnt stone slabs 6" thick	Sq. ft.		382		
Plastering with surki mortar	Sqr.		24·95		
Jelly filling below apron	C.yd.		146		
Rough stone work	,,		165		
Providing joggles	Each		39		
Total ...	...		...		
Contingencies at 5% ..	...		...		
Grand Total ...	...		...		

S. SRINIVASA AIYAR,
Executive Engineer.